

Office: Road No.8, Vishrantwadi Airport Road, Adarsh Colony, Tingre Nagar, Pune- 411032

Phone No: +91 96238 78731 | Email id: estimation@choicegoodwill.com

WO NO: GME PHASE 2- B BUILDING/ WATERPROOFING WORK-01

ANNEXURE (FINAL 01/04/2025)

Sr. No.	Description	Unit	Approx. Quantity	Rate	Amount
1.	2 & 2.5 BHK Labour Charges for Waterproofing Work- 1. Common & Master Toilet & Dry Balcony- Brickbat Waterproofing Work 2. Attach Terraces- Chemical Coating Work	Per Flat	48.00	7000.00	3,36,000.00
2.	Top Terrace + Staircase Header Room Top+ LMR Top & OHWT Top Labour Charges for Waterproofing Work- Micro Cleaning + Surface Preparation + 1:3 Angle fillet + Ghabdi work 1:3 + Brickbat 1:4 + Finish Coat + Water Stopper Curing 10 Days.	Sq.ft	4940.92	20.00	98,818.40
3.	OHWT Labour Charges for Internal Waterproofing Work- Micro Cleaning + Surface Preparation 1:3 Angle Fillet + Ghabdi Work 1:3 + 1:4 Vertical Jacket Plaster & Bottom Metal Screed Coat + Curing + water stopper Curing 10 Days.	Sq.ft	1496.28	18.00	26,933.04
4.	8th Floor Refuge Area Labour Charges for Waterproofing Work- Micro Cleaning + Surface Preparation + 1:3 Angle fillet + Ghabdi work 1:3 + Brickbat 1:4 + Finish Coat + Water Stopper Curing 10 Days.	Sq.ft	214.05	20.00	4,281.00
Total Amount					4,66,032.44

CONTRACTOR'S SIGNATURE

MR. PANDU L. MEGHAWAT

APPROVED BY

MR. AMIT ASHOK AGRAWAL

(KRISHNA BUILDCON)