

WORK ORDER NO: GOODWILL VERVE "B BUILDING" / GYPSUM PUNNING WORK-01

Date: 29/07/2024


M/s. : GULAM HUSAIN MOHAMMAD SAMI SHAIKH
Address : Sr. No. 22/2 Dhonori Road Near Dhanlaxmi Hardware Dhanori Pune- 411015
Kind Attn. : Mr. Mohammad Sami Shaikh
Contact No : 9763267582
PAN No. : PHAPS0148P
Start of work :


ARTICLE: 1 PREFACE

- 1.1 Work Order for Services on (Material + Labour) basis for the Gypsum Punning Work for M/s. Choice lifestyle- Goodwill Verve "B Building" S.No.35/36, Opposite Venkatesh Graffiti Manjari Road, Keshavnagar, Pune-411036.
- 1.2 MR. AMIT ASHOK AGRAWAL (hereinafter referred to as "DEVELOPER")
- 1.3 MR. GULAM HUSAIN MOHAMMAD SAMI SHAIKH (hereinafter referred to as "CONTRACTOR") The Contractor will be responsible for execution of the all the work in accordance to this "Work Order", in particular the detailed in article 2.
- 1.4 Total compensation: Rs. 1,79,425/- (Taxes Extra)

ARTICLE: 2 SCOPE & PERFORMANCE OF WORK CONTRACTOR

- 2.1 In general, the scope of the Contractor will include the provision of (Material + Labour) for the Gypsum Punning Work for Goodwill Verve "B-Building" as discussed and defined in the architectural drawings provided to the work contractor. Contractor will be responsible for proper fixing and installation of works, including, checking and finishing of the works.
- 2.2 The contractor rates shall include all the arrangement for Gypsum Punning Work.
- 2.3 The Contractor will ensure the proper finish of Gypsum Punning Work.
- 2.4 The Contractor will correct and replace any defects occurring within a period of one year from the date of completion or from the date of possession of the unit whichever is later. Any minor modifications and corrective works required by the End user within this period will be done by the Contractor.


Contractor's signature


Developer's Signature

WORK ORDER NO: GOODWILL VERVE "B BUILDING" / GYPSUM PUNNING WORK-01

- 2.5 Electricity for Gypsum Punning Work will be provided by the Developer. In case of construction activities after dark proper permission will be taken from the Developer representative, after displaying proper arrangement for the same. Permission of construction works at night will be totally at the discretion of the Builder and the request for same may be refused.
- 2.6 Labor Camp: Labor camp will be set up by the Contractor, as per the PBAP rules and regulations, i.e. No bamboo and chatai. Electricity and water supply for labor camp will be provided by the Developer, arrangement for the same to be made by the Contractor (Developer will provide one main supply point, further distribution will be done by the Contractor, Contractor to employ one qualified Electrician for safety and proper wiring within the labor camp). No labor will be allowed to live within the premises of the project.
- 2.7 No construction activities will be carried out without responsible contractor representative on site.
- 2.8 Contractor will be responsible for the safekeeping of his own material. The Developer will not be held responsible for any losses in terms of theft of otherwise.
- 2.9 Wastage will be the responsibility of the Contractor. Developer will not be held responsible.
- 2.10 **Completion Period**


Time is the essence of this order and hence the execution schedule should be strictly adhered to. In general, the complete **Gypsum Punning Work** for the said building will be completed. The schedule as attached in the annexure to be strictly followed.


ARTICLE: 3 COMPENSATION FOR CONTRACTOR'S WORK

- 3.1 For all the works described in this order, a fixed and firm compensation at **Rs. 1,79,425/-, In Words Rs. One Lakh Seventy-Nine Thousand and Four hundred and Twenty-Five Only** shall be given to the work contractor. The above Compensation shall include all taxes and duties & includes GST.
- The Developer, if applicable, will deduct any Tax, at source as per prevailing provisions of the law.

ARTICLE: 4 SAFETY & GENERAL RESPONSIBILITIES

- 4.1 Contractor's personnel deputed for the Work shall comply with all rules & regulations including the safety procedures prevailing at Site/ Office and shall be medically fit to perform the Work.


Contractor's signature





WORK ORDER NO: GOODWILL VERVE "B BUILDING" / GYPSUM PUNNING WORK-01

- 4.2 The Developer shall not be liable to the Contractor for any claim for loss or profits or any other consequential or indirect damages that may be suffered by the Contractor during the execution of the work.
- 4.3 Contractor shall at all-time keep the Builder fully indemnified against any consequences arising out of Work Contractor's own or on account of Contractor's default or negligence.
- 4.4 The contractor shall take all safety measures on site such as safety helmets, safety belts etc. In case of any mishap on site the contractor and only the contractor will be responsible for any consequences arising for such a situation. The contractor will not have any claim for the same.
- 4.5 No child labor will be permitted to work on site. If anyone is found the Developer has the authority to stop the work immediately. During any governmental inspection if the same is identified, the contractor will be completely responsible for the consequences.
- 4.6 **General and Statutory Obligations:**
- All statutory obligations, permits, licenses etc. in respect of the Work shall be done by the Contractor.
 - Insurances for the Contractor's personnel and Equipment as applicable and in accordance with project requirements shall be arranged by the Contractor at his own cost and will submit a photocopy of all licenses and permits to the Builders office before starting work.

ARTICLE: 5 TERMINATION OF WORK ORDER

- 5.1 The Work Order shall be terminated in case of misbehavior, disobedience, dishonesty or negligence on the part of Contractor and/or his personnel or Contractor's failure to execute, complete and deliver the Work within the specified / reasonable time as decided by the Developer. Upon any such termination, the Developer shall pay in accordance with the following:
- All amounts due and not previously paid to Contractor for Work completed in accordance with the Order prior to any notice of termination, and for Work completed thereafter as specified in the notice, after deducting an amount as may be considered suitable to adjust for loss of work caused due to the Termination.
 - The Developer has all rights, to recover from the Contractor, any loss that is incurred or foreseen due to the Contractor's default. The Developer shall not be held responsible for any damage, either direct and / or indirect, to the Work Contractor consequent on his exercising his right to early terminate or suspend the Order.


Contractor's signature


Developer's Signature

WORK ORDER NO: GOODWILL VERVE "B BUILDING" / GYPSUM PUNNING WORK-01

ARTICLE: 6 DISPUTE RESOLUTION CLAUSE


That in the event of any dispute or difference between the Party of First Part and the Party of Second Part arising out of this agreement or as to the interpretation of any terms of this Agreement, on account of any claim by or against the other or in respect of the said construction work, the same shall be referred to sole arbitrator and his decision shall be final and binding. Such arbitration shall be governed by the provisions of The Arbitration & Conciliation Act, 1996.


ARTICLE: 7 DEFECT LIABILITY PERIOD

The Defects Liability Period for the above-mentioned works shall be One year, after the completion of work. The Contractor shall rectify the defects brought to their notice during this period at their own cost. If the Contractor does not clear the defects, the Developer will be at the liberty to get the defects rectified from some other agencies and deduct the costs thereof from the payments of the Contractor.

ARTICLE: 8 MODE OF MEASUREMENTS & RATES

- 8.1 The Rate mentioned herein has been computed by the Developer and shall not be challenge by the Contractor on basis of any ambiguity in terminology or method of computation.
- 8.2 The payment schedule will be prepared by the Developer & contractor shall accept the same as per schedule prepared by the Developer.
- 8.3 **Annexure** Rates are **Exclusive** of GST as applicable and Inclusive of all other taxes, Insurance, Transportation of men material, machineries and equipment's, contractor's material loading, un-Loading, Profit etc.
- 8.4 From the Contractor's Bill amount, TDS will be deducted as per the Income Tax law applicable from time to time.
- 8.5 **Contractors' payment shall be released within 45 Days**, after verification of Invoice by Contracts/ Billing/ Execution Team as per attached documents such as Joint Measurement sheet, checklists, reconciliation report, previous amount paid verification, GST reconciliation, etc.


Contractor's signature


Developer's Signature

Office: Road No.8, Vishrantwadi Airport Road, Adarsh Colony, Tingre Nagar, Pune- 411032

Phone No: +91 96238 78731 | Email id: estimation@choicegoodwill.com

WORK ORDER NO: GOODWILL VERVE "B BUILDING" / GYPSUM PUNNING WORK-01

ARTICLE: 9 MODE OF MEASUREMENTS & RATES

Firm Name: Choice Lifestyle


Firm Address: Road No.8, Vishrantwadi-airport road, Adarsh Colony, Tingre Nagar, Pune-411032


Site Name: Goodwill Verve "B Building".

CONTRACTOR'S SIGNATURE

MR. MOHAMMAD SAMI

APPROVED BY


MR. AMIT ASHOK AGRAWAL
(CHOICE LIFESTYLE)


Contractor's signature

Labour+Material Quantity

Heaven

Sr. No.	Description	UNIT	Approx. Quantity	RATE	NET AMOUNT	A. MATERIAL		MATERIAL TOTAL	B. LABOUR		LABOUR TOTAL
						Quantity	Rate		Quantity	Rate	
1	Walls (Ground to Terrace Floor)- Gypsum Punning Work	Sq.ft	6,160	20.00	1,23,206	6,160	10.00	61,603	6,160	10.00	61,603
2	Ceiling (Ground to Terrace Floor)- Patra Finish	Sq.ft	3,411	13.00	44,342	3,411	5.00	17,055	3,411	8.00	27,287
			Total Amount		1,67,548	Budget (Material)		78,658	Budget (Labour)		88,890
			Material		78,658	Availed Budget			Availed Budget		
			Labour		88,890	Balance Budget			Balance Budget		
									Total Balance Payable		78,658

Final Course
ag/ers/jms
for
10/10/10
for
for

Uro 8877